


GD-CB(RB)-EX-C Quick Spec

GLUE DOWN MEMBRANE - COVER BOARD (RB) - EXISTING ROOF - CONCRETE DECK (RECOVER)



APPROVED COVER BOARD: DENS DECK, DENS DECK PRIME OR SECUROCK GLASS-MAT, MINIMUM 1/4" THICKNESS.

NOTES:

- 1. Attach Coverboard with Approved Insulation Adhesive. Refer to Detail Drawings "Ribbon Insulation Adhesive pattern GD-17 and GD-18".
- 2. Existing Roof types may vary and not all are acceptable. Please contact the Phoenix Technical Department for approval on layover projects prior to installation.
- 3. Class A Fire Rating with unlimited slope when utilizing Approved Coverboards.