




MECHANICALLY FASTENED MEMBRANE - INSULATION - CONCRETE DECK (NEW OR TEAR OFF)



APPROVED INSULATION: HUNTER PANELS, RMAX OR ATLAS UL CLASSIFIED INSULATION.

RoofNav Assembly Properties:	
Assembly #: 433968-0-0	Slope: 2.0000
Roof System: Single-Ply System	Wind Uplift*: 300
Application: New Roof	Internal Fire: NC
Cover Securement: Attached	Exterior Fire: A
Deck Type: Structural Concrete	Hail: SH
Assembly limited to use with noncombustible walls only: No	

NOTES:

- 1. Minimum thickness requirements may exist depending on insulation type. Please contact the Phoenix Products Technical Department for requirements if necessary.
- Attach Insulation with Concrete Fasteners and 3" Steel Insulation Plate. Refer to Detail Drawing "Fastening Pattern Insulation/Coverboard MF-7". Minimum 1" penetration.
- 3. There maybe slope restrictions regarding Fire Ratings. Please contact the Phoenix Technical Department for Fire Rating restrictions if required.