


STONE BALLASTED MEMBRANE - INSULATION - EXISTING ROOF - STEEL DECK (RECOVER)



APPROVED INSULATION: UL CLASSIFIED POLYISOCYANURATE INSULATION.

APPROVED SEPARATION SHEET: 4 OZ OR 6 OZ GEOTEXTILE SEPARATION SHEET.

NOTES:

- Loose-lay Insulation. Only install 60 or 80 mil with approved Ballasted Stone Assembly. FIELD: #4 stone @ 10 LBS. SQ./FT. PERIMETER/CORNER: #2 stone @ 13 LBS. SQ./FT.
- 2. Existing Roof types may vary and not all are acceptable. Please contact the Phoenix Technical Department for approval on layover projects prior to installation.